

MARQUETTE INTERCHANGE PIER TS7

QA/QC Lessons
Learned, Case Study

Tony F. Shkurti, PhD, SE, PE

HNTB

THE ILLINOIS TRANSPORTATION
AND HIGHWAY ENGINEERING
CONFERENCE



AGENDA



**Overview of MQIC,
bridge B-40-1231**




**The issues with
pier TS7**




**How did this
happen?**



**HNTB's Response
to the Crisis**



**Potential repair
options**



**Overview of the
reconstruction process**



Lessons Learned



**Questions/Answers/
Discussion**

NEW MARQUETTE INTERCHANGE

- Downtown Milwaukee relies on Marquette Interchange
- Wisconsin relies on Marquette Interchange





OVERVIEW OF MQIC, BRIDGE B-40-1231



Pier TS7



BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001,
Wisconsin Ave to I-43 SB
over N-E Ramp North
Face of Pier TS7





BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001,
Wisconsin Ave to I-43 SB
over N-E Ramp North
Face of Pier TS7






BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001, Wisconsin Ave to I-43 SB over N-E Ramp North Face



BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001, Wisconsin Ave to I-43 SB over N-E Ramp North Face





BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001, Pier TS7
Vertical Crack, East Face (note
location of Pot Bearing






BIANNUAL INSPECTION: PIER TS7 HAS A PROBLEM

- B-40-1231-001, Pier TS7
Vertical Crack, East Face (note
location of Pot Bearing





THE ISSUES WITH PIER TS7: Can One Tell From This?



STATE PROJECT NUMBER
1060-05-75

- NOTES**
- SEE FOLLOWING SHEETS FOR ADDITIONAL INFORMATION:
TYPICAL PIER
PIER CAP GEOMETRY
FOOTING PLANS
FOUNDATION DETAILS
SUBSTRUCTURE BELL OF BARS
ANCHOR BOLT SETTING PLAN
DOWNPOUT DETAILS
CONCRETE STAIRING DETAILS
 - PIER TS7 IS A TYPE 'TT' PIER. SEE TYPE 'TT' SHEET FOR TYPICAL PIER DIMENSIONS.
 - SPACE CAP AND PAD STIRRUP REINFORCEMENT TO CLEAR ANCHOR BOLTS.
 - PLACE BOTTOM OF CAP REINFORCEMENT TO CLEAR VERTICAL SHAFT REINFORCEMENT.
 - IF CONSTRUCTION JOINTS ARE USED IN COLUMNS, THE FIRST TIE SET IN EACH FOUR SECTION SHALL BE PLACED AT 6" ABOVE TOP OF PREVIOUS POUR.
 - MAINTAIN MINIMUM 2" CLEAR COVER TO MAIN REINFORCEMENT AT HORIZONTAL REVEAL.
 - ALL PIER CAP REINFORCEMENT IS SYMMETRICAL IN BOTH DIRECTIONS ABOUT \bar{C} PIER UNLESS SHOWN OTHERWISE.

- LEGEND**
- PLACE THESE BARS TO CLEAR BEARING ASSEMBLY ANCHOR BOLTS. SEE ANCHOR BOLT SETTING PLAN SHEET FOR BOLT LOCATIONS. MAINTAIN 3" MINIMUM HORIZONTAL CLEAR DISTANCE BETWEEN BARS. DISTRIBUTE BARS AS EVENLY AS PRACTICAL ACROSS CAP.
 - ADJUST SPACING AT TOP AS REQUIRED TO KEEP TIES BELOW PIER CAP. SLOPE TOP TIE SET TO MATCH PIER CAP WHERE POSSIBLE. TOPMOST TIE SHALL BE WITHIN 6" OF THE UNDERSIDE OF THE CAP AT ALL POINTS.
 - COLUMN BARS EXTENDING INTO THE CAP MAY BE MADE VERTICAL WHERE THEY ENTER THE CAP IN ORDER TO SIMPLIFY PLACEMENT OF THE PIER CAP REINFORCING CAGE.
 - BARS MAY EITHER BE DETAILED AND FABRICATED WITH THE REQUIRED BEND OR THEY MAY BE VERTICAL IN THE FIELD AFTER THE POUR BELOW HAS BEEN COMPLETED.

NO.	DATE	REVISION	P.J.C.	BY
1	02/24/08	CAP STIRRUP SPACING	P.J.C.	
2	02/24/08	REVISED ELEVATIONS	P.J.C.	

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-40-1231


PIER TS7

DATE: 2004
BY: WJ
PLANS: LMB
SHEET 31 OF 102
2642



THE ISSUES WITH PIER TS7:


Oooops...maybe, maybe wrong grouping






THE ISSUES WITH PIER TS7:

Ooops...maybe, maybe wrong grouping






THE ISSUES WITH PIER TS7: as meant...






THE ISSUES WITH PIER TS7: as used...






THE ISSUES WITH PIER TS7: as used...






THE ISSUES WITH PIER TS7: as used ...





THE ISSUES WITH PIER TS7: as used...






THE ISSUES WITH PIER TS7: compare...

TS6


LOCATE BARS TO CLEAR
ANCHOR BOLTS AND
PEDESTAL REINFORCEMENT



SECTION A-A

TS7

LOCATE BARS TO CLEAR
ANCHOR BOLTS AND
PEDESTAL REINFORCEMENT




SECTION A-A



THE ISSUES WITH PIER TS7: compare...


TS6

LOCATE BARS TO CLEAR
ANCHOR BOLTS AND
PEDESTAL REINFORCEMENT



TS7


LOCATE BARS TO CLEAR
ANCHOR BOLTS AND
PEDESTAL REINFORCEMENT






THE ISSUES WITH PIER TS7: compare...

Tub Girders



TS7





THE ISSUES WITH PIER TS7: Oooops again...

	CAPACITIES		SERVICE LOAD									
	Shear	Moment	Reaction		Demand				Performance ratios			
			DL	LL	V _{DL}	M _{DL}	V _{TOT}	M _{TOT}	V _{DL}	M _{DL}	V _{TOT}	M _{TOT}
	k	k-ft	k	k	k	k-ft	k	k-ft	%	%	%	%
Pier Cap	1,167	6,300	1,017	421	1,017	6,609	1,438	9,350	114.7	95.3	81.0	67
									Factored Load			
Pier Shaft		19,650						23,500				0.84
Pile Cap	1,711	8,156					589	8,780			2.9	0.93
									SERVICE LOAD			
Pile loads	Axial		Axial						Axial			
	t		t						t			
	200		285						0.7			

HNTB Response to the Crisis



- Any man can make mistakes, but only an idiot persists in his error.

Cicero

- We all make mistakes at work, it's how you react afterwards that matters

HNTB Response to the Crisis



- Immediate, with public safety as first priority
- Accepted fault once it was clear
- Got to work immediately to fix it at no expense to taxpayers

Early Response Activities

365 September 2010

	Sun	Mon	Tue	Wed	Thu	Fri	Sat
36				1	2	3	4
37	5	6	7	8	9	10	11
38	12	13	14	15	16	17	18
39	19	20	21	22	23	24	25
40	26	27	28	29	30		



365 October 2010

	Sun	Mon	Tue	Wed	Thu	Fri	Sat
40						1	2
41	3	4	5	6	7	8	9
42	10	11	12	13	14	15	16
43	17	18	19	20	21	22	23
44	24	25	26	27	28	29	30
45	31						


365 November 2010

	Sun	Mon	Tue	Wed	Thu	Fri	Sat
45		1	2	3	4	5	6
46	7	8	9	10	11	12	13
47	14	15	16	17	18	19	20
48	21	22	23	24	25	26	27
49	28	29	30				

- Received call on 9/1
- Close ramp on 9/2
- TV interview on 9/2
- Interviewed contractors 9/4 and 9/5
- Selected contractor 9/5
- Redesign began 9/5
- Initial projections ~ 4 - 5 months
- Reopened ramp in 12 weeks!!!



Early Response Activities



Potential Repair Options



- Post-tensioning and foundation retrofit, various versions \$\$
- Enhancing the pier shaft underneath the cap and foundation retrofit \$
- Replace the pier \$\$\$\$

Project Approach



TONY SHKURTI

Technical Design
Lead for Repair



PAT CASHIN

Local Office
Design Support



JIM JANKE

Led Construction
Oversight

Project Approach





- Weekly call with HNTB Executives
- Weekly call with WisDOT Executives
- Daily meetings with contractor, WisDOT bridge group and local WisDOT SE Region staff
- Once Harvey Hammond said WisDOT is getting a new pier, we were off to the races!
- Work 24/7 to reopen ramp as soon as possible



How Did this Happen?


- Final Design Discovery of Clearance Conflict
- Integral Steel Cap Beam Solution was Scrutinized
- Substructure & Superstructure Teams Parallel Path - Missed Big Picture



How Did this Happen? Column Grouping



- Column Grouping not Obvious or Transparent
- Individual Pier Designs Fully Checked-No Unique Design for TS7
- Goal: Simplify plans for similar shaped piers-Big miss on Loading






PROVE TO DOT NO OTHER ISSUES

- Report on all 258 Piers in Marquette Interchange

Prove to DOT no other Issues



- HNTB Responsible for Subconsultant Designs
- CFRP Wrap Pier Cap Shear



Prove to DOT no other Issues



- Monitor Deck Cracking before and after Jacking



RAW IMAGE FROM SCANNER




IMAGE WITH SCAN DATA



IMAGE, SCAN DATA, AND DRAFTED 3D LINES OF CRACKS





IMAGE WITH DRAFTED 3D LINES OF CRACKS



ANALYSES & DESIGN:


Where do we put the shoring towers?







ANALYSES & DESIGN:

Where do we put the shoring towers?






ANALYSES & DESIGN: Restricted traffic...






ANALYSES & DESIGN: Temporary Pier Design ...






ANALYSES & DESIGN: Temporary Pier Design ...





ANALYSES & DESIGN: Temporary Pier Design ...





DESIGN OF CHOSEN OPTION: Erected...




Analyses & Design: Fast & Furious after that...



- Designed one by one on a fast schedule:
 - Foundation
 - Header Beam
 - Shoring Frame
 - Jacking Sequence
- Designed New Pier
- Work continued at the site 24/7




ANALYSES & DESIGN: New Pier...





CONSTRUCTION: Foundation and piles for temporary...






CONSTRUCTION:
Foundation and piles for
temporary...






CONSTRUCTION: Temporary Stiffening Diaphragm...



GIRDER STIFFENING DETAIL

SECTION A-A



STIFFENER ANGLE DETAIL

NOTES

1. SHORT SLOTS VERTICAL TO FACE THE STANDARD BEAMS OF STIFFENING GIRDER WERE SHALL THROUGH BOTTOM OF SLOTTED BEAMS AS TYPED.
2. SET LARS BOTH SIDES OF WEB AND INSTALL BOLTS WITH NUTS HAND TIGHT.
3. DRIVE PAPERED BEAM EDGE SIDES OF WEB AT TOP FLANGE TO BEING OUSTANDING 1/2\"/>

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-40-1231			
CONSTR. SPEC.	2004	DESIGN BY	PLANS BY
SUPERSTRUCTURE GIRDER STIFFENING DETAILS			SHEET 5 OF 16



CONSTRUCTION: Temporary Stiffening Diaphragm...





CONSTRUCTION:
Foundation and piles for
temporary...






CONSTRUCTION: Cross Beam Size...





CONSTRUCTION: Wind Bracing...





CONSTRUCTION: Cross Beam Size...





CONSTRUCTION: Tower Sliding...





CONSTRUCTION: Jacking...

GENERAL PREPARATIONS:

1. POST OBSERVERS AT PIER T&T AND ON SUPERSTRUCTURE OVER TEMP T&T TO WATCH FOR BINDING, CRACKING OR OTHER UNUSUAL SIGNS OF UNEXPECTED DISTRESS RESULTING FROM THE JACKING OPERATION.

PIER T&T PREPARATION FOR JACKING:

1. PROVIDE POSITIVE STRAPS BETWEEN SOLE PLATES AND MASONRY PLATES TO PREVENT SEPARATION OF POT BEARINGS DURING LIFT AND DEMOLITION.
2. REMOVE NUTS FROM ANCHOR BOLTS.
3. REPLACE BOLTS BETWEEN SOLE PLATE AND BOX CAPBEAM. AT WEST BEARING REPLACE 2 3/4" BOLTS WITH 3 1/4" BOLTS. AT EAST BEARING REPLACE 2 1/4" BOLTS WITH 2 3/4" BOLTS.
4. ONLY AFTER WIND TONGUE IS IN PLACE AND JACKS ARE TIGHT AGAINST TEMPORARY SOLE PLATES, PROVIDE 3/4" TO 1 1/2" GAP BETWEEN BOLT HEAD AND SOLE PLATE. AS BRIDGE IS JACKED, USE 1/4" FEELER GAUGE BETWEEN SOLE PLATE AND BOTTOM FLANGE OF BOX CAPBEAM TO INDICATE WHEN 1/4" RAISE IS ACCOMPLISHED.

TEMP T&T JACKING PROCEDURE:

1. BRING ALL 5 JACKS TO A SNUG TIGHT CONDITION AGAINST THE TEMPORARY SOLE PLATES.
2. GIRDERS A THROUGH E SHALL BE JACKED SIMULTANEOUSLY. FOR SIMULTANEOUS JACKING, ALL JACKS SHALL BE CONNECTED THROUGH A MANIFOLD TO A SINGLE HYDRAULIC PUMP.
3. AT NO TIME SHALL ANY ONE GIRDER BE RAISED MORE THAN 1/8" HIGHER OR LAG MORE THAN 1/8" LOWER THAN ANY OTHER GIRDER DURING THE JACKING OPERATION.
4. SIMULTANEOUSLY RAISE GIRDERS TO THEIR EXPECTED HEIGHT. AS EACH GIRDER A THROUGH E REACHES ITS EXPECTED HEIGHT (OR LOAD PLUS NO MORE THAN 10 KIPS) SHUT OFF THE PUMP, RECORD THE PRESSURE, LOCK THE JACK AND CONTINUE LIFTING AT THE OTHER GIRDERS. ONCE ALL THE GIRDERS REACH THEIR EXPECTED HEIGHT, THE CONTRACTOR MAY NEED TO PERFORM JACKING OPERATIONS AT INDIVIDUAL GIRDERS TO MEET THE 1/4" CRITERIA AT PIER T&T.
5. BEFORE HYDRAULIC POWER IS RELEASED FROM THE INDIVIDUAL JACKS, THE JACKING FORCE AND HEIGHT SHALL BE RECORDED AND THE LOCKING COLLARS SHALL BE SECURELY POSITIONED TO PREVENT COLLAPSE OF THE PISTON.
6. IT IS ANTICIPATED THAT THE BRIDGE WILL BE RAISED APPROXIMATELY 5/8" TO PROVIDE 1/4" CLEAR BELOW THE BEARINGS AT PIER T&T.

EXPECTED JACKING LOAD/HEIGHT:

1. THE TABLE BELOW PROVIDES THE EXPECTED AND MAXIMUM JACKING LOADS AND HEIGHTS THAT THE CONTRACTOR IS PERMITTED. AT NO TIME IS THE CONTRACTOR PERMITTED TO EXCEED THE MAXIMUM PERMISSIBLE LOAD OR HEIGHT. IF THE EXPECTED LOAD IS EXCEEDED BY MORE THAN 10 KIPS OR EXPECTED HEIGHT IS EXCEEDED BY MORE THAN 1/4", THE CONTRACTOR WILL NOT BE PERMITTED TO OPEN THE BRIDGE TO TRAFFIC UNTIL AN EVALUATION OF THE STRESSES IN THE BRIDGE IS COMPLETED AND THE UNEXPECTED VALUES RESOLVED TO THE SATISFACTION OF THE OWNER.

GIRDER	LOAD (KIPS)		HEIGHT (INCH)	
	EXPECTED	MAXIMUM	EXPECTED	MAXIMUM
A	275	305	.625	1.375
B	330	365	.625	1.375
C	320	365	.625	1.375
D	320	395	.625	1.250
E	300	320	.625	1.000

AFTER JACKING AND PRIOR TO DEMOLITION:

1. EXCAVATE BEAM SEAT RISERS BENEATH EXISTING MASONRY PLATES.
2. CAREFULLY CUT ANCHOR BOLTS TO PREVENT DAMAGE TO MASONRY PLATES.
3. TIGHTEN BOLTS AT SOLE PLATES TO RAISE BEARING ASSEMBLY ABOVE PIER.
4. REMOVE PIER T&T IN ACCORDANCE WITH THE APPROVED PIER REMOVAL PLAN, TAKING EXTREME CARE TO PREVENT DAMAGE TO THE BEARING ASSEMBLIES.

12/14/2000		JACKING NOTES		RCW
NO.	DATE	REVISION		BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION				
STRUCTURE B-40-1231				
CONST. SPEC.	2004	DRAWN BY	RCW	PLANS CK'D.
JACKING PROCEDURE				SHEET 12 OF 18



CONSTRUCTION: Jacking...





CONSTRUCTION: Jacking...





CONSTRUCTION: Jacking...





CONSTRUCTION: Tower Protection from debris...





CONSTRUCTION: Demolition...





CONSTRUCTION: Demolition...





CONSTRUCTION: Demolition...






CONSTRUCTION: Load on Shoring tower...





CONSTRUCTION: Demolition, Salvaged Piles, New Piles...





CONSTRUCTION: New foundation...





CONSTRUCTION: Rebar cage moving in...





CONSTRUCTION: New Column...





CONSTRUCTION: Dismantle Temporary Shoring...





CONSTRUCTION: New Pier...





CONSTRUCTION: New Pier...





CONSTRUCTION: New Pier...

Lessons Learned



- Careful grouping design elements
- Clear Design Summaries - Any Doubt, Design
- Perform Early Geometric Clash Detection
- Conventional Bridges can be Complex
- QMS Senior Technical Review (Early Independent)
- PM / Task Lead should do a mandatory Cursory Review before Final
- Makes me proud how the company handled the problem
- Be truthful and fair with your Client and it will pay a dividend
- Raised HNTB's value in the eyes of WisDOT

MARQUETTE INTERCHANGE PIER TS7

QUESTIONS?